

ADDENDUM NO. 4

PARTICULARS

DATE: March 27, 2025

PROJECT: Troy University – Wallace Hall Reroof, DCM # 2025148

ARCHITECT: Seay, Seay & Litchfield, P.C. (SS&L Project No: 24174)

TO: PROSPECTIVE BIDDERS:

This Addendum is hereby made part of the Contract Documents, dated February 27, 2025, to the same extent as though it was originally included therein. Acknowledge receipt of this Addendum in the space provided in the proposal form. Failure to do so may disqualify the bidder.

1.01 CLARIFICATIONS / MODIFICATIONS:

A. Clarification to Addendum 3

- a. All insulation shall be adhered over the new self-adhered vapor barrier using low-rise foam adhesive approved by the roofing manufacturer. The self-adhered vapor barrier must be applied directly to the existing concrete deck substrate after proper cleaning and preparation.

1.02 DRAWINGS:

A. Sheet T02.00

- a. Revise Specific Demolition Note #7 to read “Contractor is responsible for demo of existing tower. The owner will have the antenna relocated from the top of the tower prior to start of demolition work. contractor to confirm with owner that antenna has been removed prior to demolishing existing tower.”

1.03 SPECIFICATIONS:

A. None

END OF SECTION

